



Addendum 1

SCC -Cherokee Parris & Peeler Buildings Exterior Water Proofing

Project Number: SCC CCC 086

11/20/2023

- 1) Will the downspouts at the Peeler Building that are in front of control joints need to be removed?
Yes, remove and reinstall as needed to do work.
- 2) Will landscape be trimmed back along buildings?
Yes, trees and bushes will be trimmed prior to work starting.
- 3) Is the parapet coping to be sealed?
No, do not seal the coping.
- 4) Does the old sealant need to be removed around the windows where the old sealant is excessively recessed?
No, leave old and seal over it. Making the front flush as normal application.
- 5) Which sealant should be used on the brick to brick, and brick to metal joints?
Use DOW 790, or better, on those, and DOW 795, or better, on wet window to glass seals.
- 6) Quote date is unchanged. Quotes are due on Tuesday 12- 05-2023, at 2:00 pm.
- 7) All forms must be used as documented on the website link.